Phone: 9717622113,

SRI GURU TEGH BAHADUR KHALSA COLLEGE

UNIVERSITY OF DELHI **DELHI-110007**

Ref. No.....

Dated: 15.04.2025

NOTICE INVITING QUOTATION

Principal SGTB Khalsa College invites sealed item rate quotations for the work of repairing of pump room of existing underground water tank of SGTB Khalsa College from experience reputed contractors having experience in similar type of work. Quotation shall be submitted in sealed cover by 28.04.2025 at 3:00 pm which shall be open on same day at 03:30 pm in office of principal SGTB Khalsa College.

WORK OF REPAIRING OF PUMP ROOM AT SGTB KHALSA COLLEGE, DELHI UNIVERSITY (CIVIL WORKS).

S.No	Description of Item	Unit	Qty
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including including disposal of rubbish to the dumping ground within 50 metres lead	sqm	125
2	Dimolishing brick work manually/ by mechanical means cum including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-incharge. In cement mortar	sqm	2
3	12 mm cement plaster of mix: 1;6(1 cement:6 fine sand) sqm 200	sqm	200
4	Brick work with common burnt clay F.P.S (non modular) cum bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shape and sizes in cement mortar 1;6(1 cement:6 coarse sand)	sqm	2
5	50mm Thick Cement concrete flooring 1:2:4(1 cement:2Sqm coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40mm thick with 20mm nominal size stone aggregate.	sqm	50
6	Removing dry or oil bound distemper, water proofing Sqm cement paint and the like by scrapping, sand papering and prepairing the surface smooth including necessary repairs to scratches etc. complete	sqm	150
7	Distempering with oil bound and washable distemper of Sqm approved	sqm	250



	brand and manufacture to give an even shade: New work (two or more coats)over and including water thinable priming coat with cement primier		
8	Painting with synthetic enamel paint of approved brand and Sqm manufacture of required cobur to give an even shade: One more coat on old work	sqm	50
9	Providing corrugated GS. Sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and GI. Limpet washers or with GI. limpet washers filled with white lead, including a coat of approved steel. primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 1.00 mm size and shape wherever required 1.00 mm thick with zinc coating not less than 275gm/m2size and shape wherever required 1.00 mm thick with zinc coating not less than 275gm/m2thick with zinc coating not less than 275gm/m2	sqm	30
10	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering lead upto 50m and lift upto 1.5m	Cum	5
11	Disposal of building rubbish / malba/similar unserviceable dismantled or waste material by mechanical means, including bading, transporting, and unbading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50m initial lead, for all leads including all lifts involved.	Cum	5
	Total Amount (Including all Taxes)		

Terms and conditions:-

- 1) Work shall be done within 10 days of issue of work order.
- 2) Work shall be done as per BOQ item and CPWD specification (Latest Edilion)
- 3) Work shall be done in such a way and the normal function of college is not disturbed.
- 4) 1% of the cost of work shall be deducted in bill of contractor for water and electricity che
- 5) TDS for I. tax and GST shall be deducted as per govt. rules.

Run, Lind-al Principal